

2

AD-A201 684

DTIC FILE COPY

OFFICE OF NAVAL RESEARCH

Contract N00014-83-K-0470-P00003

R&T Code NR 33359-718

Technical Report No. 99

Electrochemical and FTIR Spectroscopic Characterization of  
Ferrocyanide-Modified TiO<sub>2</sub> Electrodes Designed for Efficient Photosensitization

by

J. Desilvestro, S. Pons, E. Vrachnou and M. Gratzel

Prepared for publication in J. Electroanal. Chem.

Department of Chemistry  
University of Utah  
Salt Lake City, UT 84112

July 15, 1988

DTIC  
ELECTE  
NOV 14 1988  
S H D

Reproduction in whole, or in part, is permitted for  
any purpose of the United States Government

**DISTRIBUTION STATEMENT A**

Approved for public release;  
Distribution Unlimited

88 11 10 268

## REPORT DOCUMENTATION PAGE

1a. REPORT SECURITY CLASSIFICATION Unclassified			1b. RESTRICTIVE MARKINGS		
2a. SECURITY CLASSIFICATION AUTHORITY			3. DISTRIBUTION/AVAILABILITY OF REPORT Approved for public release and sale. Distribution unlimited.		
2b. DECLASSIFICATION/DOWNGRADING SCHEDULE					
4. PERFORMING ORGANIZATION REPORT NUMBER(S) ONR Technical Report No. 99			5. MONITORING ORGANIZATION REPORT NUMBER(S)		
6a. NAME OF PERFORMING ORGANIZATION University of Utah		6b. OFFICE SYMBOL (if applicable)	7a. NAME OF MONITORING ORGANIZATION		
6c. ADDRESS (City, State, and ZIP Code) Department of Chemistry Henry Eyring Building Salt Lake City, UT 84112			7b. ADDRESS (City, State, and ZIP Code)		
8a. NAME OF FUNDING/SPONSORING ORGANIZATION Office of Naval Research		8b. OFFICE SYMBOL (if applicable)	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER N00014-83-K-0470-P00003		
8c. ADDRESS (City, State, and ZIP Code) Chemistry Program, Code 1113 800 N. Quincy Street Arlington, VA 22217			10. SOURCE OF FUNDING NUMBERS		
			PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.
11. TITLE (Include Security Classification) Electrochemical and FTIR Spectroscopic Characterization of Ferrocyanide-Modified TiO <sub>2</sub> Electrodes Designed for Efficient Photosensitization					
12. PERSONAL AUTHOR(S) J. Desilvestro, S. Pons, E. Vrachnou and M. Gratzel					
13a. TYPE OF REPORT Technical		13b. TIME COVERED FROM 9/87 TO 7/88		14. DATE OF REPORT (Year, Month, Day) July 15, 1988	
15. PAGE COUNT 24					
16. SUPPLEMENTARY NOTATION					
17. COSATI CODES			18. SUBJECT TERMS (Continue on reverse if necessary and identify by block number)  infrared spectroelectrochemistry, ferricyanide		
FIELD	GROUP	SUB-GROUP			
19. ABSTRACT (Continue on reverse if necessary and identify by block number)  Attached.					
20. DISTRIBUTION/AVAILABILITY OF ABSTRACT <input checked="" type="checkbox"/> UNCLASSIFIED/UNLIMITED <input type="checkbox"/> SAME AS RPT <input type="checkbox"/> DTIC USERS			21. ABSTRACT SECURITY CLASSIFICATION Unclassified		
22a. NAME OF RESPONSIBLE INDIVIDUAL Stanley Pons			22b. TELEPHONE (Include Area Code) (801)581-4760		22c. OFFICE SYMBOL

ABSTRACT

The mechanism of the photosensitization of  $\text{TiO}_2$  by adsorbed ferrocyanide has been investigated by electrochemical measurements and surface FTIR spectroscopy. It is shown that surface roughness factors of approximately 100–200 are necessary for efficient light harvesting. Ferrocyanide adsorbates on titania are compared to  $\text{Ti}(\text{Fe}(\text{CN})_6)^{4-}$  films deposited by a novel electrochemical method onto metallic substrates. Cyclic voltammetry and analysis of the infrared vibrational spectra of  $\text{TiO}_2\text{-Fe}(\text{CN})_6^{4-}$  surface complexes and  $\text{Ti}(\text{Fe}(\text{CN})_6)^{4-}$  indicate significant charge transfer from  $\text{Fe}^{II}$  to  $\text{Ti}^{IV}$ . Ferrocyanide adsorption geometries are proposed on the basis of experimental data and geometric considerations of the anatase lattice. Light conversion efficiencies are discussed, and a model energy level diagram for the semiconductor/sensitizer/electrolyte interface is presented.

Titanium dioxide. (m) jru.



--	--

## ELECTROCHEMICAL AND FTIR SPECTROSCOPIC CHARACTERIZATION OF FERROCYANIDE-MODIFIED $\text{TiO}_2$ ELECTRODES DESIGNED FOR EFFICIENT PHOTSENSITIZATION

JOHANN DESILVESTRO \* and STANLEY PONS

*Department of Chemistry, University of Utah, Salt Lake City, UT 84112 (U.S.A.)*

ERSI VRACHNOU and MICHAEL GRÄTZEL

*Institut de Chimie Physique, Ecole Polytechnique Fédérale, CH-1015 Lausanne (Switzerland)*

(Received 2nd December 1987)

### ABSTRACT

The mechanism of the photosensitization of  $\text{TiO}_2$  by adsorbed ferrocyanide has been investigated by electrochemical measurements and surface FTIR spectroscopy. It is shown that surface roughness factors of approximately 100–200 are necessary for efficient light harvesting. Ferrocyanide adsorbates on titania are compared to  $\text{Ti}[\text{Fe}(\text{CN})_6]$  films deposited by a novel electrochemical method onto metallic substrates. Cyclic voltammetry and analysis of the infrared vibrational spectra of  $\text{TiO}_2\text{-Fe}(\text{CN})_6^{4-}$  surface complexes and  $\text{Ti}[\text{Fe}(\text{CN})_6]$  indicate significant charge transfer from  $\text{Fe}^{\text{II}}$  to  $\text{Ti}^{\text{VI}}$ . Ferrocyanide adsorption geometries are proposed on the basis of experimental data and geometric considerations of the anatase lattice. Light conversion efficiencies are discussed, and a model energy level diagram for the semiconductor/sensitizer/electrolyte interface is presented.

### INTRODUCTION

Recently, we have described efficient photosensitization of  $\text{TiO}_2$  surfaces by adsorption of tris(2,2'-bipyridyl-4,4'-dicarboxylate)ruthenium(II) [1], carboxylated porphyrins [2], and  $\text{Fe}(\text{CN})_6^{4-}$  [3]. The latter system is of particular mechanistic interest since ferrocyanide shows little optical absorption above 360nm. However, brick-red coloration, obtained upon interaction of  $\text{Fe}(\text{CN})_6^{4-}$  with  $\text{TiO}_2$ , is shown to be due to charge transfer complexation between  $\text{Ti}^{4+}$  and this anion.

Prussian blue [4] and its analogues [5],  $\text{M}_x[\text{M}'(\text{CN})_6]$ , (with M or  $\text{M}' = \text{V}$  [6], Co [7], Ni [8], Cu [9], Ru [10], Cd [11]), have been studied extensively. However, only a few reports [7,12] describe brown to orange colored compounds obtained upon

\* Present address: Swiss Federal Institute for Reactor Research CH-5303 Würenlingen, Switzerland.

mixing acidic  $\text{Ti}^{4+}$  or  $\text{Ti}^{3+}$  solutions with  $\text{Fe}(\text{CN})_6^{4-}$  or  $\text{Fe}(\text{CN})_6^{3-}$  solutions. On the basis of X-ray diffraction data and Mössbauer spectra, Milligan and co-workers [7.12b] suggested a structure of  $\text{Ti}^{\text{IV}}[\text{Fe}^{\text{II}}(\text{CN})_6]$ , even when  $\text{TiCl}_3$  and  $\text{Fe}(\text{CN})_6^{3-}$  were used as the starting material.  $\text{Ti}[\text{M}(\text{CN})_6]$ , with  $\text{M} = \text{Co}, \text{Rh}, \text{Ir}$ , have been characterized by X-ray diffraction, IR, optical, and X-ray photoelectron spectroscopy [13].

It is therefore appropriate to present an analysis of the electrochemical and infrared spectroscopic analysis of ferrocyanide complexes at titania surfaces. In the first part we will treat the electrochemistry of the semiconductor/surface complex/electrolyte interface and discuss relationships between surface roughness and monochromatic photocurrent efficiencies. The effect of hydroquinone as a cosensitizer will also be discussed. In the second part, we treat the interaction of  $\text{Fe}(\text{CN})_6^{4-}$  and  $\text{TiO}_2$  in terms of the results of electrode surface FTIR spectroscopy. We demonstrate here a novel method for the preparation of  $\text{Ti}[\text{Fe}(\text{CN})_6]$  films deposited on gold and platinum electrodes, and compare them to analogous species formed at titania surfaces. These results provide new information on the structure of the  $\text{TiO}_2\text{-Fe}(\text{CN})_6^{4-}$  complex and the mechanism of photosensitization of semiconductor surfaces.

## EXPERIMENTAL

### Materials

Titanium metal sheet (0.5 mm thickness, Kobe Steel, Ltd.; nominal impurity analysis O (0.099%), Fe (0.078%), C (0.014%), H (0.0035%), and N (0.002%)) was used as the metallic electrode substrate. For dispersed electrode measurements,  $\text{TiO}_2\text{-P25C}$  powder obtained from Degussa (W. Germany, BET area  $55 \text{ m}^2 \text{ g}^{-1}$ ) was used. The relative crystalline distribution was 80% anatase and 20% rutile. All chemicals were at least reagent grade and were used as supplied. Deionized water was filtered through activated charcoal and triply distilled. All solutions were deaerated with Ar or  $\text{N}_2$  prior to use.

### Electrodes

Pt, Au, and Ti disk electrodes were sealed into glass tubes with silicon glue or epoxy and polished with increasingly finer grades of alumina (down to  $0.05 \mu\text{m}$ ). Finally, the surfaces were briefly ultrasonicated in distilled water. The preparation of ca.  $20 \mu\text{m}$  thick  $\text{TiO}_2$  layers (anatase) on Ti rods (6 mm in diameter) has been described previously [2,14]. Surface oxide roughness factors exceeding 100 were obtained by preparing the surfaces in a 50% humidified atmosphere. Thin polycrystalline  $\text{TiO}_2$  films were obtained by scanning the potential of a Ti electrode, immersed in  $0.1 \text{ M H}_2\text{SO}_4$ , at  $10 \text{ mV s}^{-1}$  from  $-0.5$  to  $3.0 \text{ V}$  (vs. SCE) and to  $6.0 \text{ V}$ . No oxide film was observed visually for films formed with the scan to  $+3.0 \text{ V}$ , whereas polarizations to  $+6.0 \text{ V}$  resulted in the formation of films which exhibited a golden interference color. This is in agreement with similar experiments by



tion For

GRA&I ☒

AB ☐

anced ☐

ention

Distribution/

Availability Codes

Avail and/or  
Dist Special

A-1

Blackwood [15], who estimated the film thicknesses to be 10 nm at 3.0 V and 20 nm at 6.0 V.

TiO<sub>2</sub> surface complexation was effected in the dark by exposing TiO<sub>2</sub> electrodes to Ar-deaerated solutions of 0.01 M HClO<sub>4</sub> with 0.01 M K<sub>4</sub>Fe(CN)<sub>6</sub> for 5 h. The 20 μm thick anatase layers thereupon exhibited a slight brick-red color. No visible color change was observed after ferrocyanide adsorption on thin TiO<sub>2</sub> films prepared by electrochemical oxidation of titanium substrates. Before characterization, the electrodes were thoroughly rinsed with 0.01 M HClO<sub>4</sub> and distilled water and dried in vacuo.

Ti[Fe(CN)<sub>6</sub>] on gold and platinum were prepared by electrochemically induced precipitation of the complex ion, similar to the preparation of corresponding colloidal compounds that has been described previously [7,12b]. The corresponding metal working electrode was immersed in 10 ml of deaerated mechanically stirred 0.06–0.12 M K<sub>3</sub>Fe(CN)<sub>6</sub> solution. The electrode potential was switched to 0.0 V and 10 ml of 0.06–0.12 M TiCl<sub>4</sub> in 6 M HCl was injected into the cell. The reduction current dropped to zero within the range 50 s (for 0.06 M) to 5 s (for 0.12 M) whereupon a yellow film appeared. Prussian blue films were prepared according to the method of Itaya et al. [4b].

#### *Apparatus*

Electrochemical experiments were carried out in standard two- or three-compartment electrochemical cells. Cells for photoelectrochemical or infrared spectroelectrochemical measurements were equipped with flat Pyrex or CaF<sub>2</sub> windows, respectively, and have been described previously [16]. For driving the electrochemical experiments, a HI-TEK Model DT 2101 potentiostat was used with a HI-TEK Model PPR1 waveform generator and a Houston Model 200 XY recorder. All potentials were measured and are quoted versus the saturated calomel electrode (SCE).

TiO<sub>2</sub> electrodes were illuminated with radiation from a 55 W tungsten-halogen lamp dispersed through a monochromator (Bentham Model M300). Monochromatic photocurrent efficiencies were determined by a calibrated Si photodiode. The detector was covered by a mask which was of the same size as the electrode. Polychromatic irradiation, provided by the same lamp, which was low-frequency attenuated by a 14 cm thickness water filter and high-frequency limited by a 490 nm cutoff filter. The light intensities were measured with a Scientech Model 362 power energy meter.

Infrared reflectance spectra were obtained with a Bruker FT-98 vacuum spectrometer modified for surface studies, as has been described previously [16]. For the mid-infrared region, a KBr beamsplitter, a KBr optical bench window, and a 77 K cooled HgCdTe detector were employed in the measurements. Interferograms were recorded at a resolution of 4 cm<sup>-1</sup>; the optical bench was maintained at pressures (< 120 Torr), where interferences due to atmospheric absorbance was insignificant. The sample chamber was purged with dry nitrogen. The difference vibrational reflectance spectrum was obtained by ratioing the average of up to 2000 spectra of the sample surface with the same number of spectra of the untreated surface.

## RESULTS AND DISCUSSION

*Electrochemical behavior in the dark*

Figure 1 presents current-potential curves for a ca. 20  $\mu\text{m}$  thick  $\text{TiO}_2$  layer (anatase) in 0.01  $M$   $\text{HClO}_4$ . In the dark, the unmodified  $\text{TiO}_2$  electrode exhibits the typical behavior of an n-type semiconductor with reversible charging of the space charge layer (dashed curve). The same voltammograms were obtained in the




Fig. 1. Current-potential curves for polycrystalline  $\text{TiO}_2$  (anatase) in 0.01  $M$   $\text{HClO}_4$  in the dark, before (---) and after (—, - - - -) ex situ complexation with  $\text{Fe}(\text{CN})_6^{4-}$ . Scan rate was  $50 \text{ mV s}^{-1}$ . The solid trace was obtained after 1 h in 0.01  $M$   $\text{HClO}_4$  at 1 V under room light irradiation; the dotted curve under the same conditions, but with additionally 0.01  $M$  hydroquinone in the solution. The inset shows photocurrents under monochromatic illumination (450 nm, photon flux =  $3.9 \times 10^{-11} \text{ mol s}^{-1} \text{ cm}^{-2}$ ) of the same  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$  electrode in 0.01  $M$   $\text{HClO}_4$  + 0.01  $M$  hydroquinone at 0.2 V.

presence of 0.01 *M* hydroquinone. After surface complexation with  $\text{Fe}(\text{CN})_6^{4-}$ , increased cathodic currents were measured for  $E < 0.9$  V in 0.01 *M*  $\text{HClO}_4$  and a cathodic wave appeared with a peak potential at about 0.04 V. The anodic currents increased only slightly, and did not show an oxidation wave. This result can be explained if we assume a slow electron transfer to the hexacyanoferrate species through the space charge layer of the semiconductor operated in the depletion mode. It is possible that the peak potential of this reduction is far negative of the standard potential of the surface complex since the electron transfer kinetics at polycrystalline semiconductors is kinetically controlled in a complex way by the magnitude of the band bending, the charge transfer through the Helmholtz layer, and the mass transfer conditions [17].

The magnitude of the cathodic peak current at potentials  $> 0.5$  V depended critically on the optical saturation of the electrode. After 30 to 60 min room light illumination at 1.0 V, maximum surface oxidation was attained (cf. also fig. 2 below). Subsequent voltammetry of this surface in the dark resulted in the response shown by the solid trace in Fig. 1. Visually, no color change could be observed at the surface during the oxidation.

If the  $\text{Fe}(\text{CN})_6^{4-}$ -modified  $\text{TiO}_2$  was held at 1.0 V in the presence of 0.01 *M* hydroquinone, the observed reduction currents were significantly smaller (dotted curve in Fig. 1). This result indicates that the oxidized  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$  complex is reduced by hydroquinone ( $E^\circ = 0.44$  V at pH = 0 [18]) and that hydroquinone can act as a cosensitizer in photochemical experiments (see below). From this result we estimate a lower limit for  $E^\circ$  of the surface species to be  $\approx 0.4$  V.

The chemisorption of  $\text{Fe}(\text{CN})_6^{4-}$  was also studied at dispersions of  $\text{TiO}_2$  particles (cf. also ref. 3).  $\text{TiO}_2$  powder was stirred in an aqueous solution of  $10^{-4}$  to  $10^{-2}$  *M*  $\text{K}_4\text{Fe}(\text{CN})_6$  in  $10^{-2}$  *M*  $\text{HClO}_4$ . After equilibration for 5 h under an Ar atmosphere, we collected the  $\text{TiO}_2$  by centrifugation. The concentration of free  $\text{Fe}(\text{CN})_6^{4-}$  was determined by cyclic voltammetry of the supernate. A saturation coverage of  $7 \times 10^{-5}$  mol  $\text{g}^{-1}$   $\text{TiO}_2$  or  $1.3 \times 10^{-10}$  mol  $\text{cm}^{-2}$  was calculated. This surface concentration corresponds to slightly less than one molecular monolayer coverage, which may be due to deviation from the assumption of close-packing surface orientation or to the micropores being too small for penetration by  $\text{Fe}(\text{CN})_6^{4-}$ .\*

The saturation coverage of the titania surfaces and the data presented in Fig. 1 may be used for determining the electrochemically active area of  $\text{TiO}_2$  electrodes. Generally, the surface roughness of a polycrystalline semiconductor electrode cannot be determined from impedance measurements unless the minority carrier density can be determined independently, e.g. from Hall and bulk resistivity measurements. In the case of  $\text{TiO}_2$  (anatase), electron microscopy yielded only qualitative data on the electrochemically active area [19]. Recently we showed, however, that the surface roughness factor of polycrystalline  $\text{n-WO}_3$  can be esti-

semiconductors

\* Assuming a radius of 0.46  $\mu\text{m}$  for  $\text{Fe}(\text{CN})_6^{4-}$ , a close-packed monolayer corresponds to  $2.3 \times 10^{-10}$  mol  $\text{cm}^{-2}$  and, in the case of a one-electron transfer, to  $2.2 \times 10^{-5}$  C  $\text{cm}^{-2}$ .

mated by adsorption of a suitable ion and subsequent voltammetric measurements [17b].

In order to obtain meaningful data from such an approach, at least three conditions have to be fulfilled:

(i) The saturation coverage should correspond to one monolayer. Thus charged and rather spherical molecules are preferable.

(ii) The adsorbate has to be stable at the pH values required for adsorption. The pH has to be below the isoelectric point of the semiconductor for adsorption of an anion and above for a cation.

(iii) The adsorbate has to undergo a redox reaction with a standard potential at more positive values than the flat band potential in the case of an n-type semiconductor.

Requirements (i) to (iii) are fulfilled for the system  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$  in slightly acidic solutions. From the shaded area in Fig. 1 which corresponds to  $3.1 \text{ mC cm}^{-2}$  and by assuming a monomolecular coverage of around  $1.8 \times 10^{-10} \text{ mol cm}^{-2}$  (see above) we conclude that the electrochemically active area is around 180 times higher than the apparent geometrical area.

#### *Photoelectrochemical behavior*

The inset in Fig. 1 shows photocurrents obtained under monochromatic irradiation (wavelength  $\lambda = 450 \text{ nm}$ ) of a  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$  electrode in  $0.01 \text{ M HClO}_4$ ,  $0.01 \text{ M}$  hydroquinone at a potential of  $0.2 \text{ V}$ . The monochromatic photocurrent efficiency (defined as electron flux divided by photon flux) corresponds to 26% which is in agreement with earlier reported values (cf. Fig. 2 in ref 3). One of the electrodes showed, however, a significantly lower efficiency, 7% at  $450 \text{ nm}$ . Interestingly, its electrochemically determined surface roughness factor of ca. 40 was also much lower than for the electrode presented in Fig. 1. This finding further corroborates the necessity of high surface area electrodes for efficient dye sensitization [1-3] and explains the much lower sensitization efficiencies reported for single crystals and low area polycrystalline electrodes [20].

The effect of hydroquinone as a cosensitizer is demonstrated in Fig. 2. Without hydroquinone (lower curve) the photocurrents decreased exponentially during the first 100 s of polychromatic illumination ( $\lambda > 490 \text{ nm}$ ). The apparently slower decay afterwards may partly be due to sub-bandgap effects of the  $\text{TiO}_2$  electrode (cf. Fig. 2 in ref 1) and partly due to slow cation (probably proton) migration out of the fractal structure of the electrode. The oxidation charge during 5 min of irradiation corresponded to  $1.7 \text{ mC cm}^{-2}$  or to only 55% conversion of the ferrocyanide film. In the presence of hydroquinone however (upper curve), the photocurrents stabilized at  $0.046 \text{ mA cm}^{-2}$  after an induction period of around 40 s. After 2 h of continuous illumination the photocurrents were still as high as  $0.044 \text{ mA cm}^{-2}$ , which illustrates the efficiency of hydroquinone to reduce the oxidized surface complex.

Light intensities of  $58 \text{ mW cm}^{-2}$  ( $\lambda > 420 \text{ nm}$ ) resulted in an initial photocurrent density of  $0.32 \text{ mA cm}^{-2}$  in  $0.1 \text{ M}$  hydroquinone at pH 2. Within 17 h of




Fig. 2. Photocurrent-time behavior for the  $\text{TiO}_2$  electrode presented in Fig. 1. Polychromatic ( $\lambda > 490$  nm) irradiance was  $6.5 \text{ mW cm}^{-2}$ . The  $0.01 \text{ M HClO}_4$  solution was deaerated with  $\text{Ar}$  during illumination. Lower curve: no hydroquinone; upper curve:  $0.01 \text{ M}$  hydroquinone in  $0.01 \text{ M HClO}_4$ .

Fig. 3. Surface reflectance FTIR spectra of various ferrocyanide complexes. All spectra were obtained under vacuum. (a)  $\text{Fe}(\text{CN})_6^{4-}$  chemisorbed on a  $20 \mu\text{m}$   $\text{TiO}_2$  layer (anatase). (b)  $\text{Fe}(\text{CN})_6^{4-}$  chemisorbed on an electrochemically generated film of ca.  $20 \mu\text{m}$   $\text{TiO}_2$  on  $\text{Ti}$ . Only p-polarized IR radiation was analyzed. (c)  $\text{Ti}[\text{Fe}(\text{CN})_6]$  film on gold prepared by adding a  $0.12 \text{ M TiCl}_4 + 6 \text{ M HCl}$  solution to a pre-electrolyzed ( $0.0 \text{ V}$ )  $0.12 \text{ M K}_3\text{Fe}(\text{CN})_6$  solution. (d) Prussian blue on gold prepared at a constant cathodic current density of  $0.01 \text{ mA cm}^{-2}$  for  $60 \text{ s}$  in  $0.01 \text{ M FeCl}_3 + 0.01 \text{ M K}_3\text{Fe}(\text{CN})_6$  ( $\text{pH } 2$ ). Cyclic voltammetry revealed a surface charge of  $1.08 \text{ mC cm}^{-2}$ .

polychromatic irradiation the current dropped to  $0.11 \text{ mA cm}^{-2}$ . From the total charge of  $9.0 \text{ C cm}^{-2}$  driven through the cell we calculate a turnover number of ~~290~~ 3000, demonstrating the photocatalytic behavior of  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$ .

### Surface FTIR spectroscopic investigations

Figure 3a shows the infrared difference reflectance spectrum of the  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$  modified electrode measured under vacuum; the unmodified  $\text{TiO}_2$  electrode (ca. 20  $\mu\text{m}$  anatase) is the reference. The rather broad peak at  $2078\text{ cm}^{-1}$  (full width at half maximum,  $\text{FWHM} = 24\text{ cm}^{-1}$ ) is due to C-N stretching modes. The peak frequency is intermediate between ferrocyanide ( $2040\text{ cm}^{-1}$ ) and ferricyanide ( $2114\text{ cm}^{-1}$ ) in neutral aqueous solution [21], which indicates that there is a significant charge transfer from ferrocyanide to  $\text{TiO}_2$ -units ( $x < 2$ ) on the electrode surface. The shoulder at  $2045\text{ cm}^{-1}$ , which persists even after prolonged washing with 0.01  $M$   $\text{HClO}_4$  and  $\text{H}_2\text{O}$ , may indicate the presence of physisorbed ferrocyanide within the surface  $\text{TiO}_2$  layer. These spectral features, as well as the brick-red coloration disappear completely after soaking the electrode in 0.1  $M$   $\text{NaOH}$  for 24 h. In situ infrared spectroscopic investigations of these surfaces proved difficult due to their low reflectivity (methods of investigation included the use of parabolic collection optics placed close to the sample, careful focussing, and varying the range of angles of incidence). After emersion of  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$  electrodes which had been prepolarized at 0.3 or 1.0 V, and subsequent washing with  $\text{H}_2\text{O}$ , the open circuit potential drifted to values around 0.2 to 0.4 V when the electrodes were placed again in 0.01  $M$   $\text{HClO}_4$ . This indicates that emersed films are probably a mixture of chemisorbed  $\text{Fe}(\text{CN})_6^{4-/3-}$ . No significant spectral differences could be resolved for  $\text{TiO}_2$  electrodes emersed at  $-0.3$  or 1.0 V, respectively.

Titanium electrodes covered by a film of 10 to 20 nm of electrochemically formed  $\text{TiO}_2$  exhibit metallic reflectivity. After complexation of this surface with  $\text{Fe}(\text{CN})_6^{4-}$  for 5 h, a band appears at  $2073\text{ cm}^{-1}$  in the infrared reflectance spectrum collected under vacuum (Fig. 3b). Peak frequency and shape are very similar to the  $2078\text{ cm}^{-1}$  band of 20  $\mu\text{m}$   $\text{TiO}_2$  layers. Due to lower surface roughness, however, the peak intensity is more than ten times lower than that observed for titania presented in Fig. 3a. No adsorption was apparent from conventional cyclic voltammetric analysis, probably due to sluggish electron transfer kinetics through the passivating  $\text{TiO}_2$  films. No spectral changes were apparent during in situ spectroelectrochemical measurements. On  $\text{TiO}_2$  single crystals (rutile, donor density  $= 10^{19}\text{ cm}^{-3}$ ) no ferrocyanide adsorption was detected using either electrochemical or infrared spectroscopic techniques.

In the light of the above observations, it is obviously important to compare the electrochemical and infrared spectroscopic behavior of  $\text{Ti}[\text{Fe}(\text{CN})_6]$  with  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$ . We therefore adopted a previously described precipitation method [7,12b] in order to deposit  $\text{Ti}[\text{Fe}(\text{CN})_6]$  films onto metal substrates. Cyclic voltammograms in 0.5  $M$   $\text{KNO}_3$  showed a completely irreversible oxidation wave, peaking at 0.83 V. After two or three scans between 0.0 and 0.9 V, the oxidation wave and also the coloration of the electrode disappeared completely; voltammograms typical of the unmodified substrates were then prevalent, indicating complete dissolution of the film upon anodic oxidation.

Figure 3c shows an ex situ spectrum of a  $\text{Ti}[\text{Fe}(\text{CN})_6]$  film on gold prior to oxidation. We note, an asymmetric band with a maximum at  $2106\text{ cm}^{-1}$  and a FWHM of ca.  $45\text{ cm}^{-1}$ . This band disappeared completely after oxidation of the ferrocyanide film at 1.0 V. The same results were obtained with gold and platinum substrates. More detailed electrochemical and in situ IR spectroscopic data on  $\text{Ti}[\text{Fe}(\text{CN})_6]$  films will be presented elsewhere.

X-ray data for powdered  $\text{Ti}[\text{Fe}(\text{CN})_6]$  [7,12b] revealed the same face-centered cubic unit cell (space group  $F_{m3m}/O_h^2$ ) as determined for Prussian blue [22]. Therefore we also included a reflection spectrum of Prussian blue, deposited on gold, in Fig. 3d. The spectra presented in Fig. 3c and 3d show exactly the same peak frequency. However, on the basis of the very different electrochemical behavior and the different coloration, there remains no doubt that the two samples are chemically different. Similar IR spectra of Prussian blue with a broad asymmetric band centered at  $2080\text{--}2090\text{ cm}^{-1}$  have been reported in the literature [23].

#### Structural and mechanistic implications

If  $\text{TiO}_2$  is covered by only one monolayer of " $\text{Fe}(\text{CN})_6^{4-}$ ", the surface complex is expected to have a different structure than  $\text{Ti}[\text{Fe}(\text{CN})_6]$ . This is supported experimentally by the different infrared and electrochemical results. The behavior of the




Fig. 4. Proposed geometries for  $\text{Fe}(\text{CN})_6^{4-}$  adsorbates bonded via 3 cyano nitrogens to  $\text{TiO}_2$  (anatase). Only Ti cores are shown in the tetragonal anatase titanium dioxide lattice.

CN stretching modes indicate a higher degree of charge transfer from ferrocyanide to  $\text{Ti}^{\text{IV}}$  in the case of formation of  $\text{Ti}[\text{Fe}(\text{CN})_6]$  and suggest that the ferrocyanide units are less readily oxidized in  $\text{Ti}[\text{Fe}(\text{CN})_6]$  than in the case of  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$ . We conclude from the irreversible oxidation wave at 0.8 V for the former complex that the  $E^\circ$  value for  $(\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-})$  is less than 0.8 V.

The question arises if ferrocyanide is bonded to the surface oxide by 1, 2, or 3 cyano nitrogens. The CN bond is expected to weaken (with respect to solution  $\text{O}_2$  symmetry) because of coordination to Ti centers. This decrease in bond strength seems to be more than compensated for by the lower occupancy of the  $\text{II}_{\text{CN}}^*$  orbital due to decreased electron density of the Fe core. Model calculations [24] have shown that the  $F_{1u}$  mode splits according to the symmetry of the surface complex and as a function of binding energy. The largest blueshifts (compared to  $\text{O}_2$  symmetry) are expected when binding occurs through one or two nitrogens to the surface. From the present data however, a blue-shift of  $38 \text{ cm}^{-1}$  for  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$  (cf. ref. 21 for free  $\text{Fe}(\text{CN})_6^{4-}$ ) cannot be related unambiguously to coordination geometry and binding energy.




Fig. 5. Energy level diagram. The donor and acceptor states of the cosensitizer ( $\text{H}_2\text{Q}/\text{Q}$ ) and the sensitizer (S) in its ground and excited states are represented schematically by Gaussian distribution functions.  $E_c$ ,  $E_f$ , and  $E_v$  denote the potentials of conduction band, valence band, and Fermi level, respectively.

The following qualitative conclusions can be drawn by considering the  $\text{Fe}(\text{CN})_6^{4-}$  and the  $\text{TiO}_2$  geometry. From the crystal structure of Prussian blue with a lattice constant of 1 nm [4b] we conclude that the Ti cores, which bind ferrocyanide via two or three N atoms, have to be separated by at least 0.7 nm. The tetragonal structure of anatase with the lattice parameters  $a = b = (0.3785 \pm 0.0002)$  nm and  $c = (0.9514 \pm 0.0006)$  nm [25] offers many possibilities for  $\text{Fe}(\text{CN})_6^{4-}$  coordination to 2 Ti atoms separated by 0.757 nm. Figure 4 shows that even coordination via 3 N is feasible based on geometric considerations. Further adsorption studies as well as electrochemical and IR-spectroscopic measurements on various  $\text{TiO}_2$  (anatase, rutile) samples are needed to investigate the adsorbate geometry.

On the basis of the band positions of  $\text{TiO}_2$  (anatase) [26] and the optical [3] and electrochemical properties (see above) of  $\text{TiO}_2/\text{Fe}(\text{CN})_6^{4-}$ , an approximate energy level diagram can be drawn for the semiconductor/sensitizer/electrolyte interface (Fig. 5). Even at wavelengths as long as 650 nm the driving force for electron injection to the  $\text{TiO}_2$  conduction band is fairly high ( $> 0.5$  eV), resulting in quantum efficiencies of up to 37% [3]. On the other hand, overall energy conversion efficiencies of photosensitized photoelectrochemical cells will be limited by the rather high overpotential for electron injection. Excited states of other transition metal cyanides forming charge-transfer complexes with  $\text{TiO}_2$  may match the semiconductor conduction band energetically in a more favorable way. Such compounds are presently being investigated.

#### ACKNOWLEDGEMENTS

We thank the Office of Naval Research and the Fonds National Suisse de la Recherche Scientifique for support of this work.

#### REFERENCES

- 1 J. Desilvestro, M. Grätzel, L. Kavan, J. Moser and J. Augustynski, *J. Am. Chem. Soc.*, 107 (1985) 2988.
- 2 K. Kalyanasundaram, N. Vlachopoulos, V. Krishnan, A. Monnier and M. Grätzel, *J. Phys. Chem.*, 91 (1987) 2342.
- 3 E. Vrachnou, N. Vlachopoulos and M. Grätzel, *J. Chem. Soc. Chem. Commun.*, (1987) 868.
- 4 (a) D. Ellis, M. Eckhoff and V.D. Neff, *J. Phys. Chem.*, 85 (1981) 1225; (b) K. Itaya, T. Ataka and S. Toshima, *J. Am. Chem. Soc.*, 104 (1982) 4767.
- 5 For a review, see: A. Ludi and H.U. Güdel, *Struct. Bonding* (Berlin), 14 (1973) 1.
- 6 (a) D. Shaojun and L. Fengbin, *J. Electroanal. Chem.*, 217 (1987) 49; (b) *ibid.*, 210 (1986) 31.
- 7 K. Maw, Jr., M.L. Beasley, R.L. Collins and W.O. Milligan, *J. Am. Chem. Soc.*, 90 (1968) 3201.
- 8 (a) S. Sinha, B.D. Humphrey and A.B. Bocarsly, *Inorg. Chem.*, 23 (1984) 203; (b) B.D. Humphrey, S. Sinha and A.B. Bocarsly, *J. Phys. Chem.*, 91 (1987) 586.
- 9 (a) L.M. Spierko and T. Kuwana, *Electrochim. Acta*, 32 (1987) 765; (b) E.W. Grabner and S. Kalvelke-Mohn, *J. Appl. Electrochem.*, 17 (1987) 653.
- 10 K. Itaya, T. Ataka and S. Toshima, *J. Am. Chem. Soc.*, 104 (1982) 3751.
- 11 H. Rubin, D.J. Arent, B.D. Humphrey and A.B. Bocarsly, *J. Electrochem. Soc.*, 134 (1987) 93.
- 12 (a) Gmelins Handbuch der Anorganischen Chemie, 8. Auflage, Eisen, Teil B, Verlag Chemie GmbH, Berlin, 1930, pp. 604, 646; (b) H.B. Weiser, W.O. Milligan and J.B. Bates, *J. Phys. Chem.*, 46 (1942) 99.

Güdel x

- 13 H. Inoue and E. Fluck, *Z. Naturforsch. Teil B*, 39 (1984) 185.
- 14 C. Stalder and J. Augustynski, *J. Electrochem. Soc.*, 126 (1979) 2007.
- 15 D.J. Blackwood, Ph.D. Thesis, University of Southampton, 1986.
- 16 See for example; (a) A. Bewick and S. Pons in (C. Hester (Ed.), *Advances in Infrared and Raman Spectroscopy*, Hayden, London, 1985, p. 1; (b) J. Foley and S. Pons, *Anal. Chem.*, 57 (1985) 945A.
- 17 (a) J. Desilvestro, M. Grätzel and T. Pajkossy, *J. Electrochem. Soc.*, 133 (1986) 331; (b) J. Desilvestro, Ph.D. Thesis, Swiss Federal Institute of Technology, Lausanne, Switzerland, 1985.
- 18 M.P. Soriaga and A.T. Hubbard, *J. Am. Chem. Soc.*, 104 (1982) 2735.
- 19 (a) M. Koudelka, A. Monnier, J. Sanchez and J. Augustynski, *J. Mol. Catal.*, 25 (1984) 295; (b) M. Grätzel in E. Pelizzetti and N. Serpone (Eds.), *Homogeneous and Heterogeneous Photocatalysis*, NATO ASI Series, Vol. 174, Reidel, Dordrecht, 1986, p. 105.
- 20 Cf. refs. 2a-n and 3a-i in ref. 1.
- 21 S. Pons, M. Datta, J.F. McAlear and A.S. Hinman, *J. Electroanal. Chem.*, 160 (1984) 369.
- 22 J.F. Keggin and F.D. Miles, *Nature (London)*, 137 (1936) 577.
- 23 (a) R.E. Wilde, S.N. Ghosh and B.J. Marshall, *Inorg. Chem.*, 9 (1970) 2512; (b) J.W. Childers, A. Crumbliss, P.S. Lugg and R.A. Palmer, *J. Phys. Colloq.*, C6 (1983) 285; (c) K. Niwa and K. Doblhofer, *Electrochim. Acta*, 31 (1986) 439.
- 24 C. Korzeniewski, M.W. Severson, P.P. Schmidt, S. Pons and M. Fleischmann, *J. Phys. Chem.*, in press.
- 25 R.C. Weast (Ed.), *CRC Handbook of Chemistry and Physics*, 59th ed., CRC Press, West Palm Beach, 1978-1979, p. B240.
- 26 J. Moser and M. Grätzel, *J. Am. Chem. Soc.*, 105 (1983) 6547.

TECHNICAL REPORT DISTRIBUTION LIST, GEN

	<u>No. Copies</u>		<u>No. Copies</u>
Office of Naval Research Attn: Code 1113 800 N. Quincy Street Arlington, Virginia 22217-5000	2	Dr. David Young Code 334 NORDA NSTL, Mississippi 39529	1
Dr. Bernard Douda Naval Weapons Support Center Code 50C Crane, Indiana 47522-5050	1	Naval Weapons Center Attn: Dr. Ron Atkins Chemistry Division China Lake, California 93555	1
Naval Civil Engineering Laboratory Attn: Dr. R. W. Drisko, Code L52 Port Hueneme, California 93401	1	Scientific Advisor Commandant of the Marine Corps Code RD-1 Washington, D.C. 20380	1
Defense Technical Information Center Building 5, Cameron Station Alexandria, Virginia 22314	12 high quality	U.S. Army Research Office Attn: CRD-AA-IP P.O. Box 12211 Research Triangle Park, NC 27709	1
DTNSRDC Attn: Dr. H. Singerman Applied Chemistry Division Annapolis, Maryland 21401	1	Mr. John Boyle Materials Branch Naval Ship Engineering Center Philadelphia, Pennsylvania 19112	1
Dr. William Tolles Superintendent Chemistry Division, Code 6100 Naval Research Laboratory Washington, D.C. 20375-5000	1	Naval Ocean Systems Center Attn: Dr. S. Yamamoto Marine Sciences Division San Diego, California 92132	1

ABSTRACTS DISTRIBUTION LIST, SDIO/IST

Dr. Robert A. Osteryoung  
Department of Chemistry  
State University of New York  
Buffalo, NY 14214

Dr. Douglas N. Bennion  
Department of Chemical Engineering  
Brigham Young University  
Provo, UT 84602

Dr. Stanley Pons  
~~Department of Chemistry~~  
~~University of Utah~~  
Salt Lake City, UT 84112

Dr. H. V. Venkatesetty  
Honeywell, Inc.  
10701 Lyndale Avenue South  
Bloomington, MN 55420

Dr. J. Foos  
EIC Labs Inc.  
111 Downey St.  
Norwood, MA 02062

Dr. Neill Weber  
Ceramatec, Inc.  
163 West 1700 South  
Salt Lake City, UT 84115

Dr. Subhash C. Narang  
SRI International  
333 Ravenswood Ave.  
Menlo Park, CA 94025

Dr. J. Paul Pemsler  
Castle Technology Corporation  
52 Dragon Ct.  
Woburn, MA 01801

Dr. R. David Rauh  
EIC Laboratory Inc.  
111 Downey Street  
Norwood, MA 02062

Dr. Joseph S. Foos  
EIC Laboratories, Inc.  
111 Downey Street  
Norwood, Massachusetts 02062

Dr. Donald M. Schleich  
Department of Chemistry  
Polytechnic Institute of New York  
333 Jay Street  
Brooklyn, New York 01

Dr. Stan Szpak  
Code 633  
Naval Ocean Systems Center  
San Diego, CA 92152-5000

Dr. George Blomgren  
Battery Products Division  
Union Carbide Corporation  
25225 Detroit Rd.  
Westlake, OH 44145

Dr. Ernest Yeager  
Case Center for Electrochemical  
Science  
Case Western Reserve University  
Cleveland, OH 44106

Dr. Mel Miles  
Code 3852  
Naval Weapons Center  
China Lake, CA 93555

Dr. Ashok V. Joshi  
Ceramatec, Inc.  
2425 South 900 West  
Salt Lake City, Utah 84119

Dr. W. Anderson  
Department of Electrical &  
Computer Engineering  
SUNY - Buffalo  
Amherst, Massachusetts 14260

Dr. M. L. Gopikanth  
Chemtech Systems, Inc.  
P.O. Box 1067  
Burlington, MA 01803

Dr. H. F. Gibbard  
Power Conversion, Inc.  
495 Boulevard  
Elmwood Park, New Jersey 07407

ABSTRACTS DISTRIBUTION LIST, SDIO/IST

Dr. V. R. Koch  
Covalent Associates  
52 Dragon Court  
Woburn, MA 01801

Dr. Randall B. Olsen  
Chronos Research Laboratories, Inc.  
4186 Sorrento Valley Blvd.  
Suite H  
San Diego, CA 92121

Dr. Alan Hooper  
Applied Electrochemistry Centre  
Harwell Laboratory  
Oxfordshire, OX11 0RA UK

Dr. John S. Wilkes  
Department of the Air Force  
The Frank J. Seiler Research Lab.  
United States Air Force Academy  
Colorado Springs, CO 80840-6528

Dr. Gary Bullard  
Pinnacle Research Institute, Inc.  
10432 N. Tantan Avenue  
Cupertino, CA 95014

Dr. J. O'M. Bockris  
Ementech, Inc.  
Route 5, Box 946  
College Station, TX 77840

Dr. Michael Binder  
Electrochemical Research Branch  
Power Sources Division  
U.S. Army Laboratory Command  
Fort Monmouth, New Jersey 07703-5000

Professor Martin Fleischmann  
Department of Chemistry  
University of Southampton  
Southampton, Hants, SO9 5NH UK